ATG4 SYSTEM – LRU REMOVAL AND INSTALLATION

1. ABS CONTROL PROCESSOR UNIT (ACPU/ACPU-2) REMOVAL (TASK 44-20-00-010-801)

　　A.　General

　　　　(1)　This procedure has this task:
　　　　　　(a)　Removal of the ACPU/ACPU-2 unit.

　　B.　References

　　　　(1)　Gogo IPCS Section 46-41-XX

　　C.　Fixtures, Tools, Test, and Support Equipment

REFERENCE	QUANTITY	DESIGNATION
N/A	AR	Safety Clip — Circuit Breaker
N/A	AR	Standard Issue Tools

　　D.　Access

　　　　(1)　The ACPU / ACPU-2 is located on the XXX Rack/Shelf.

　　E.　Job Setup

　　　　(1)　Open, safety, and tag the circuit breakers:

PANEL	DESIGNATION	LOCATION
PX-X	BXX	Flight Deck
PX-X	CXX	Flight Deck

　　F.　Get Access

　　　　(1)　Get access to the XXX Rack/Shelf.